

GLOBAL PORTABLE BUILDINGS
Transportable Multi-Purpose Buildings
(All Portable Buildings are new.)
RETAIL PRICE LIST
FOB NEW ORLEANS EAST YARD
January, 2007

8' x 20' GENESIS **\$16,867.00**

Includes: AC volt electrical system (breaker panel, 3 light fixtures, wall receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room. Can sleep 8 people with double bunk beds.

8' x 40' GENESIS **\$26,550.00**

Includes: AC volt electrical system (breaker panel, 6 light fixtures, wall receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room. Can sleep 16 people with double bunk beds.

8' x 20' ESSENTIAL with Bathroom **\$21,705.00**

Includes: AC volt electrical system (breaker panel, 3 light fixtures, wall receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room.
Bathroom; Includes bathroom wall with sliding pocket door, toilet, shower, sink, cabinet, plumbing, etc. Note; Hot water heater not included, but plumbed for.

8' x 40' ESSENTIAL with Bathroom **\$29,985.00**

Includes: AC volt electrical system (breaker panel, 6 light fixtures, wall receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room.
Bathroom: Includes bathroom wall with sliding pocket door, toilet, Shower, sink, cabinet plumbing, etc. Note: Hot water heater not included, but plumbed for.

8' x 20' ESSENTIAL with Bathroom and Kitchen \$19,680.00

Includes: AC volt electrical system (breaker panel, 3 light fixtures, Wall receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 inches of rigid insulated finished walls/ceilings, vinyl floor covering and utility room.

Bathroom: Includes bathroom wall with sliding pocket door, toilet, shower, sink, cabinet, plumbing, etc. Note; Hot water heater not included, but plumbed for.

Kitchen: Includes 6' counter top, sink with faucets, cabinets, plumbing, etc.

8' x 40' ULTIMATE with Bathroom, Kitchen and Bedroom/Office \$29,340.00

Includes: AC electrical system (breaker panel, 6 light fixtures, wall Receptacles, phone hookup, wiring, etc.), windows, entrance door and 2 Inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room.

Bathroom; Includes bathroom wall with sliding pocket door, toilet, shower, sink, cabinet, plumbing, etc. Note; Hot water heater not included, but plumbed for.

Kitchen: Includes 6' counter top, sink with faucets, cabinets, plumbing, etc.

Note: Hot water heater not included, but plumbed for.

bedroom/Office: Includes: Wall with locking door, closet with shelves and sliding closet doors.

OPTIONS:

BEDROOM/OFFICE 8' x 40' GENESIS ESSENTIAL \$ 1,350.00

Includes: Wall with locking door, closet with shelves and sliding closet doors.

SOLAR SYSTEM for 8' x 40' GENESIS/ESSENTIAL/ULTIMATE \$3,870.00

Includes: 150 Watt Polycrystalline silicon solar panel, controller/regulator, (3) 12 volt DC adaptor plug, (4) 12 volt 100 amp maintenance free batteries.

SOLAR SYSTEM FOR 8' X 40' GENESIS, ESSENTIAL, ULTIMATE \$4,492.50

Includes: 150 watt Polycrystalline silicon solar panel, controller/regulator, (6) 12 volt DC adaptor plug, (8) 12 volt (100 amp) maintenance free batteries.

SIX PERSON BUNK HOUSE

8' x 40' Six Person Bunk House **\$35,100.00**

Includes: (3) double bunk beds with (6) mattresses, (2) bathrooms (each with toilet, shower, plumbing, etc. Hot water heater not included but plumbed for.), 3 sinks, 3 entrance doors, 3 tables/desks with chairs, 3 sets of double standing steel lockers, 3 sets of swing out enclosures for window A/C units, AC volt electrical system (breaker panel, light fixtures, wall receptacles, phone hookup, wiring, etc.), windows and 2 inches of rigid insulated finished walls/ceiling, vinyl floor covering and utility room.

SHOWER AND TOILET UNITS:

(3) 8' x 40' HIGH CUBE UNITS CONNECTED **\$71,985.00**

Includes: AC volt electrical system (breaker panel, light fixtures, wall receptacles, wiring, etc.) windows, entrance doors, 2 inches of rigid insulated finished walls, finished ceiling and vinyl floor covering.

ADDITIONAL 8' x 40' CENTER SECTIONS TO (3) 8' x 40' UNITS **\$19,485.00/ea.**

The center sections have no sidewalls, but are reinforced with a minimum of (2) heavy-duty steel posts and reinforced top and bottom rails.

STORAGE UNITS:

8' x 10' FOLDABALE STORAGE CONTAINERS **\$ 3,150.00**

2,000 pounds 1 mm thick galvanized steel.

Includes: Forklift pockets and double door.

Note: (16) Storage Units folded can fit on (1) 40' flatbed truck for shipping.

ALL PORTABLE BUILDINGS ARE NEW.